



Prospec Limited

Tel: 01709 377147

To complete the clause, select the appropriate wording from below. Highlighted text can be 'dragged and dropped' to save typing.

K13 RIGID SHEET FINE LININGS/PANELLING

160 PROPRIETARY PANEL LINING SYSTEM

Prospec Ltd manufacture a range of panel lining systems. Click on the name below to jump to the product and specification details.

Marathon Duct Panelling (Pre fabricated)

A panelling system to match Marathon Cubicle systems (see NBS clauses K32/112, 120 and 130). Designed to be installed in a single visit with other trades in attendance, in conjunction with adjoining cubicles.

Materials and fittings for Marathon Cubicle and Vanity systems are selected for their durability and resistance to water and chemicals, to withstand wet use, the rigours of cleaning and to deter vandals.

Compact grade laminate panels, suitable for "wet" areas are resistant to water and chemicals designed to withstand the rigours of cleaning and to deter vandals.

High pressure laminate-faced chipboard suitable for "Dry" areas.

The 10mm and 12mm thick compact/solid laminate panels are available in a choice of standard colours from Formica large sheet ranges. Access, fascia and end panels and lighting pelmets are also available.

Panel layout:

Standard up to 2400mm high 3no panels.

Above 2400mm to a maximum of 4000mm 4no panels.

Panel sizes to suit actual sanitary ware specification.

Optional cistern mounting detail.

Direct fixing of urinals and wash hand basins.

Panel widths to suit cubicle layout.

Panels fixed on 2-part lift off steel clips to WPB framework, 4 / 6 no per panel with concealed fixings using stainless steel screws.

Framework: 18mm WPB sections, exposed faces (shadow gaps) in composite high-pressure laminate.

Fixings from stainless steel.

Built onto plinth from timber with adjustment packing pieces to accommodate uneven floor levels.

Designed to be installed in a single site visit with co-ordinated sanitary ware and pipework supplied and installed by other specialist contractor, and co-ordinated with installation of associated cubicles were applicable.

Installed by Prospec employees.

Consult Prospec Ltd technical literature for details and colour availability. Prospec also offer a design services with CAD drawings and it is recommended that they are consulted early in the design process. Marathon Cubicles are installed by Prospec Contracts.

Panels:

Manufacturer: Prospec Limited, PO Box 48, Canklow Meadows Estate, West Bawtry Road, Rotherham, S60 2XP, Tel: 01709 377147, Fax: 01709 375239, Web: www.prospec.co.uk E-mail: marathon@prospec.co.uk

Product reference: Marathon Duct panel system

Frame: Prefabricated WPB plywood frame.

Panel height: ... mm - insert as necessary - usually 3 no panels in full height system up to 2400mm high. For heights up to 4000mm consult with Prospec Ltd for recommendations and details.

Board/ Panel type:

Compact grade laminate

Thickness: 10mm / 12mm

Core material: Not applicable

Facing: Pre-finished - **Colour:** - select from manufacturer's range availability.

Edge treatment: Machined edge with chamfer to all edges.

High pressure laminate faced chipboard

Thickness: 18mm

Core material: Moisture resistant chipboard.

Facing: Melamine faced - **Colour:** - select from manufacturer's range availability.

Edge treatment: Edged all round in 2mm PVC or post formed on vertical edges with 2mm PVC edges to horizontals.

Installation:

Method of fixing panels: 2-part lift off zinc plated steel clips to timber framework – 4 / 6 no per panel (delete as necessary) with concealed fixings using stainless steel screws.

Joint treatment: Vertical and horizontal shadow bands formed from HPL bonded to 18mm WPB plywood.

Included features: Part-height cistern covers with matching tops.